K.C.T. Consultancy Services

Soil Testing and Material Testing

(State & Central Govt. Approved) Regd. No.: AB/TC/Ren/E-I/5294

O.No. AB-Tender-5604-2012

NABL (ISO/IEC: 17025) Accredited (scope of our accreditation available on www.nabl-india.org)



Ref. No.:

RCT/MC/13/04/04~003/07/CT)

Date:

04/04/13

Test Report

To,

Pericon Primix Pvt.Ltd.

Ref: Your letter dated 12/02/2013

Sample ID: Colour Putty

Sub:-Testing of Wall Putty Sample supplied by you

Dear Sir,

Please find herewith test result of wall putty sample supplied by you

Sr. No.	Description	Test Results
1	Compressive strength in Mpa at 28 days	9.86
	Setting time	
	Initial Setting Time in min.	165.00 .
	Final Setting Time in min.	450.00
3	Tensile Adhesion strength in Mpa	1.00
4	Water absorption (%)	1.30

Remark:-1) The sample was tested after addition of 45% water by weight for all test as per instrcution giver by the client

- 2) The test for compressive strength was done on cube sample of size 70.6x70.6x70.6mm, and cubes tested as per procedure mentioned in IS: 516. Test for IST and FST was done as per perocedure mentioned in IS: 4031-Part 5
- 3) Results reflect the properties of sample supplied to us.
- 4) Results certificate not be used for publicity / Product promotion. Results shall not be reproduced except in full.
- 5) We do not undertake or We are not bound to participate or appear in any legal court matter or litigation on any issues what so ever.
- 6) Tested sample may be preserved only for 15 days time unless otherwise requested.

Thanking you,

Yours faithfully,

For KCT Consultancy Services.,

(Dr. K.C. Thaker

LXXVII

00⊠aranar